

State of Kansas



15.093.20007.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 19 1967

CONSERVATION DIVISION
Wichita, Kansas

4-19-67

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Lacey of Beardmore Drlg. Co. has this
date requested permission to plug the following described well:

Mr. Lacey guarantees payment of the plugging fee.

Operator's full Name: Beardmore Drilling Company

Complete Address: 700-120 Bldg., Wichita, Kansas

Lease Name: Waterhouse "A" Well No. 2

Location: NE NE Sec. 21 Twp. 21 Rge. 21 XX
(E) (W)

County Hodgeman Total Depth 4314' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lacey was instructed to plug the well as follows:

8 5/8" to 392' circulated w/ Cement. T.D. 4314
Mud 4314' to 700' Spotted 30 sacks cement 700' to 600'
Mud 600' to 440' Spotted 30 sacks cement 440' to 340'
Mud 340' to 45' Plug, Hulls & 15 sacks cement 45' to 0'

Very truly yours,

Edward J. Lova
Conservation Division Agent