

State of Kansas



15.083.30100.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 22 1966
CONSERVATION DIVISION
Wichita, Kansas
11-22-66

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Lacey of Beardmore Drilling Co. has this date requested permission to plug the following described well:

Mr. Lacey guarantees payment of the plugging fee.

Operator's full Name: Beardmore Drilling Company

Complete Address: 700-120 Building, Wichita, Kansas

Lease Name: Bauer "A" Well No. 1

Location: NE SW Sec. 21 Twp. 21 Rge. 21 (X) (W)

County Hodgeman Total Depth 4370' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lacey was instructed to plug the well as follows:

- 8 5/8" to 392' circulated w/ cement. T.D. 4370'
- Mud 4370' to 700' Spotted 40 sacks cement 700' to 580'
- Mud 580' to 390' Spotted 30 sacks cement 390' to 290'
- Mud 290' to 45' Plug, H 11s & 10 sacks cement 45' to 0'

Very truly yours,

Edgar J. Eves
Conservation Division Agent