



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

November 8, 1981

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Tim Kohlous of Damac Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: GulFco Production, Inc.

Complete Address: 1900 W. Loop South, Suite 1900, Houston, Texas

Lease Name: Hauschild Well No. 1-15

Location: 200' EWL 650' NSL NW Sec. 15 Twp. 21 Rge. 7 (E) (W)

County: Rice Total Depth: 3470

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated:

Mr. Kohlous was instructed to plug the well as follows:

8 5/8" - 200' - 175 sacks - Circulate and Fill hole with mud. Pump
50 sacks cement through drill pipe at 300'. Fill hole with
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap
hole with 10 sacks cement. Cement rat hole with 10 sacks
cement. Cement mouse hole with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1981

Very truly yours,

CONSERVATION DIVISION
Wichita Kansas

Arthur M. Loren
Conservation Division Agent

11-17-1981