

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Rush SEC. 9 TWP. 19 RGE. 20W E/W 12
Location as in quarters or footage from lines:
NW NE NE

Locate Well
correctly on above
Section Platt.

Lease Owner Rains & Williamson Oil Company, Inc.
Lease Name Bellport A-1 Well No. _____
Office Address 435 Page Court Bldg. 220 W. Douglas, Wicht, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 6-3-83
Plugging completed 6-17-83
Reason for abandonment of well or producing formation _____

_____ Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom _____ T.D. 4252'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	406'	none
				5-1/2"	4246'	536.50'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with sand to 4200' and ran 5 sacks cement. Shot casing @2820',
2005', 1030', 635' and 530'. Pulled a total of 17 joints of 5-1/2" casing.
Plugged well with 3 hulls, 15 gel, 70 cement, 15 gel, 1 hulls, plug and 150
cement, 60/40 pos, 2% gel, 3% cc.
Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of June, 19 83

My Commission expires:



Irene Hoover
RECEIVED
Notary Public.

JUN 21 1983 6-21-83

WELL LOG (15.165.20490.00.00


COMPANY Rains & Williamson Oil Co., Inc.

SEC. 9 T. 19S R. 20W
 LOC. NW NE NE

FARM Bellport "A" NO. 1
 (Twin)

RIG. NO. 4

TOTAL DEPTH 4247'



COMM. 2-15-74

COMP. 2-24-74

CONTRACTOR Rains & Williamson Oil Co., Inc.

CASINO


20 10'
 15 8-5/8" @ 406' with 250 sx. common, ELEVATION 2233 KB
 12 6 2% gel
 13 5-1/2" @ 4246' with 150 sx. 60/40 pos, PRODUCTION oil
 18% salt, 3/4 of 1% CFR2
FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Clay and Post Rock	70
Shale and Shells	200
Shale	416
Sand and Shale	725
Shale	900
Sand	1100
Shale and Red Bed	1456
Anhydrite	1491
Shale	2175
Shale and Lime	2368
Lime and Shale	2530
Shale and Lime	2835
Lime and Shale	2970
Shale and Lime	3115
Lime and Shale	3260
Shale and Lime	3362
Lime and Shale	3730
Shale and Lime	3875
Lime	4247
<u>Rotary Total Depth</u>	<u>4247</u>

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 02 1983
 CONSERVATION DIVISION
 Wichita, Kansas

State of KANSAS
 County of SEDGWICK ss:

I, Wilson Rains, President of the Rains & Williamson Oil Co., Inc.
 upon oath state that the above and foregoing is a true and correct copy of the log of the Bellport "A" (Twin) #1 well.



Wilson Rains
 WILSON RAINS
 19 74
Juanita M. Green
 NOTARY PUBLIC
 Juanita M. Green

Subscribed and sworn to before me this 26th day of February
 My Commission Expires: October 4, 1975