

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD
OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH

**Locate well correctly on above
Section Plat**

State Corporation Commission
800 Blitting Building
Wichita, Kansas

County. Sec. 30 Twp. 19S Rge. (E) 19 (W) Rush

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NE $\frac{1}{4}$ NE $\frac{1}{4}$ NE $\frac{1}{4}$

Lease Owner I-S-T Drilling Co., Inc.

Lease Name Knotts-Seltmann Well No. 1

Office Address 1316 Union National Bank Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 8-18 19 49

Application for plugging filed 8-18 19 49

Application for plugging approved 8-18 19 49

Plugging commenced 8-18 19 49

Plugging completed 8-18 19 49

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production none 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Box 207, Great Bend, Kansas

Producing formation - - - Depth to top Bottom Total Depth of Well 4721 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Filled with heavy mud to 158'. Plug, 10 Sacks of cement. Filled with mud to 30', and plugged with wood plug. Filled to base of cellar with cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....
Address.....

STATE OF Kansas, COUNTY OF Sedgewick, ss.
Scott Stuckey (employee of owner) or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
 described well as filed and that the same are true and correct. So help me God. L. S. T. Drilling Co., Inc.

(Signature)

1316 Union National Bank Bldg., Wichita 2, Kansas

SUBSCRIBED AND SWORN to before me this.....18th.....day of
 1952

to before me this.....13th.....day of
My commission expires March 25, 1952

My commission expires.....~~February 11, 1950~~

22-2625

2-48-15M

AUG 20 1949

Notary Public.

PLUGGING
FILE SEC 30 T 19 R 19
PAGE 110 LINE 19

ST. LOUIS
COMMISSION
August 2

8-20-49

DRILLING LOG

FCC

To: L-S-T Drilling Co., Inc
1316 Union National Bank Building
Wichita 2, Kansas

County: Rush, Kansas
Section: 30-19S-19W
Location: C NE/4 NE/4 NE/4

Lease: Knotts-Seltmann #1

Rotary Total Depth: 4741'

Commenced: 7-27-49; Completed: 8-13-49

Casing: 8-5/8" @ 160'; 5-1/2" none-dry

Contractor: L-S-T Drilling Co., Inc.
1316 Union National Bank Building
Wichita 2, Kansas

FIGURES INDICATE BOTTOM OF FORMATION

0	to	35	Clay
35		60	Sand and Gravel
60		390	Shale and Shells
390		440	Red Bed
440		452	Sand
452		504	Red Bed
504		720	Shale and Shells
720		825	Red Bed
825		880	Shale and Red Bed
880		1110	Sand, Shale, Streaks & Pyrite
1110		1315	Red Bed and Shale
1315		1484	Red Bed
1484		1515	Anhydrite
1515		1980	Shale and Shells
1980		2045	Salt and Shale
2045		2380	Shale and Shells
2380		2650	Lime
2650		2695	Shale and Shells
2695		2780	Broken Lime
2780		2865	Lime
2865		2875	Lime and Shale
2875		2931	Broken Lime
2931		3120	Lime
3120		3190	Broken Lime
3190		3302	Shale and Broken Lime
3302		3366	Lime
3366		3450	Broken Lime
3450		3928	Lime
3928		3981	Lime and Chert
3981		4194	Lime
4194		4272	Conglomerate
4272		4314	Shale and Lime
4314		4481	Conglomerate
4481		4570	Cherty Lime
4570		4631	Sandy Lime
4631		4646	Sand and Chert
4646		4698	Lime and Dolomite
4698		4711	Shale and Sand
4711		4741	T.D. - Dolomite and Chert

Tops: Heebner 3793
Lansing-Kansas City 3838
Mississippi 4440
Viola 4608
Simpson 4698
Arbuckle 4711

RECEIVED

AUG 20 1949

ST
WICHITA, KANSAS

PLUGGING
RUSH SEC. 30 T. 19 S. R. 19 W.
LOG PAGE 110 LINE 19

Page #2

Drilling Log - Knotts-Seltmann #1, Sec. 30-19S-19W, Rush County, Kansas

STATE OF KANSAS

SS:

COUNTY OF SEDGWICK

I, the undersigned, being duly sworn on oath, state that the above statement and log is true and correct record and log of the well drilled at the location above described.

L-S-T DRILLING CO., INC.

By

Scott Shuckey

Subscribed and sworn to before me this 19th day of August, 1949.

My commission expires March 25, 1952

Catherine Lacey
Notary Public