

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Rush County, Sec. 26 Twp. 19S Rge. 16 (E) (W)

Location as "NE/CNW/SW" or footage from lines C-SE-NW-NE

Lease Owner Cooperative Refinery Ass'n.-Inter. Cooperative Petroleum Ass'n.

Lease Name Hemken "B" Well No. 1

Office Address Box 765 Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed September 24 19 55

Application for plugging filed September 24 19 55

Application for plugging approved September 25 19 55

Plugging commenced September 26 19 55

Plugging completed September 26 19 55

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Horner

Producing formation Depth to top Bottom Total Depth of Well 3805 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1068	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud from 3805 to 300'. Set 1st Halliburton plug set at 300', 1/3 sacks hulls, cemented with 20 sacks. Top plug set at 35', 1/3 sacks hulls, cemented with 10 sacks cement to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Company Rig #5
Address Box 765 Great Bend, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.
P. H. Jackson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) P. H. Jackson
Box 765 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27 day of September 19 55

My commission expires September 2, 1959

Ruth Whove Notary Public.

PLUGGING
FILE SEC 26 T 19 R 16 W
BOOK PAGE 3 LINE 39

RECEIVED
CORPORATION COMMISSION
SEP 29 1955
9-29-55
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

Hemken "B" #1

Loc: C/SE-NW-NE
 Sec: 26-19S-16W
 Rush County, Kansas
 Operator: Cooperative Refinery Ass'n.
 Contractor: Company Rig #5

Elevation: 2018 D.F.
 Casing: 8 5/8" at 1068 with 525
 sx. posmix, 4 C.C.

Comm: 9-10-55 Comp: 9-25-55
 T.D: 3805

<u>From</u>	<u>To</u>	<u>Formation</u>
0	275	Surface hole
275	450	Shale and shells
450	590	Sand
590	665	Shale and shells
665	930	Red bed and shale
930	1058	Red bed
1058	1087	Anhydrite
1087	1890	Shale and shells
1890	2000	Shale and lime
2000	2205	Lime and shells
2205	2440	Lime and shale
2440	2535	Lime
2535	2640	Lime and shale
2640	2825	Shale
2825	3135	Shale and lime
3135	3215	Lime
3215	3270	Lime and shale
3270	3325	Shale, lime, sand
3325	3385	Lime
3385	3450	Shale and lime
3450	3805	Lime
3805		R.T.D.

(STATE OF KANSAS)

(COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of the log on the
 Hemken "B" #1 well, located C-SE-NW-NE of Section 26-19S-16W, Rush County, Kansas.

P. A. Jumper

Subscribed and sworn to before me this 27 day of September 1955.

Ruth Whove

My commission expires: September 2, 1959

PLUGGING
 FILE SEC. 26-19-R-16W
 BOOK PAGE 3 LINE 29

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 27 1955
 INSPECTION DIVISION