


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rice County. Sec. 5 Twp. 21S Rge. 9W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SW NW

Lease Owner Lebsack Oil Production, Inc.
Lease Name Moore #1 Well No. 1
Office Address P. O. Box 489, Hays, Kansas 67601
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above Section Plat

Dry Hole
Date Well completed September 13, 1979 19
Application for plugging filed September 13, 1979 19
Application for plugging approved September 13, 1979 19
Plugging commenced 1:00 PM, September 13, 1979 19
Plugging completed 2:30 PM, September 13, 1979 19
Reason for abandonment of well or producing formation

Dry Hole
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3379'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	217.54'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud.
Heavy mud to 500' with 40 sacks through drill pipe;
heavy mud to 210' with 25 sacks through drill pipe;
heavy mud to 40' with How co plug, 1/4 sack hulls,
solid bridge with 10 sacks to surface; 2 sacks in rathole.

9/20/79 SEP 20 1979
RECEIVED
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner
STERLING DRILLING COMPANY
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of September, 19 79



Charles M. Hall
Charles M. Hall, Notary Public.

My commission expires

STERLING DRILLING COMPANY
P. O. Box
Sterling, Kansas 67579

WELL LOG ----- MOORE #1

Located: SW NW, Section 5-21S-9W, Rice County, Kansas

OWNER: Lebsack Oil Production, Inc.

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

SCOMMENCED: September 6, 1979

COMPLETED: September 13, 1979

TOTAL DEPTH: 3379'

LOG

SCASING RECORD

0 - 219 Sand, Shale and Red Bed.
219 - 1205 Shale
1205 - 2245 Lime and Shale
2245 - 3379 Lime

Ran 7 joints used 24#, 8 5/8" casing,
206.54' set at 217.54' D.B. with 200
sacks 60/40 Pozmix with 3% cc. Plug down
at 3:45 PM, 9-6-79, by Showco.

Plugged.

Deviation Surveys: 3/4° at 2062'
1° at 3360'

RECEIVED
STATE CORPORATE COMMISSION

SEP 20 1979

CONSERVATION DIVISION
Wichita, Kansas