

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rice County, Sec. 5 Twp. 21 Rge. 9 (E) (W) X

Location as "NE/CNW%SW%" or footage from lines NE SE SW

Lease Owner Specter Pipe & Supply, Inc.

Lease Name Schafer Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 8-26-62 19

Application for plugging filed March 30, 1972 19

Application for plugging approved April 3, 1972 19


Plugging commenced 4-24-72 19

Plugging completed 5-3-72 19

Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gib Thoman

Producing formation Kansas City Depth to top 2950 Bottom 3234 Total Depth of Well 3385 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE "	PUT IN	PULLED OUT
				8 5/8" OD	202 ft.	none
				5 1/2" OD	3385 ft.	2461.10

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

plug back to 2900 ft. dump 5 sacks cement; mudded hole to 200 ft. set 10 ft. rock bridge; dumped 25 sacks cement; mudded to 40 ft. set 10 ft. rock bridge; dumped 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

MAY 22 1972

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAY 15 1972

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Lynch Casing Pulling Company
Address R.R. 4, Gt. Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

Specter Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

[Signature]
Russell, Kansas
(Address)

(SUBSCRIBED) AND SWORN to before me this 19th day of March, 1972



April 1972

Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY


15.159.00625.0000

Company- THOS. H. ALLAN
Farm- Schafer No. 1

SEC. 5 T. 21 R. 9W
NE SE SW

Total Depth. 3385'
Comm. 8-13-62 Comp. 8-26-62
Shot or Treated.
Contractor. Mull Drilling Co., Inc.
Issued. 12-8-62

County Rice
KANSAS



CASING:
8 5/8" 202' cem w/180 sx.
5 1/2" 3384' cem w/150 sx.

Elevation. 1691' RB

Production. 26 BOPD

Figures Indicate Bottom of Formations.

(All depths from RB)

soil & sand	60
red beds	800
salt & shale	1150
anhydrite & shale	1250
shale	1400
lime & shale	1600
shale & shells	2161
lime, Tarkio	2178
shale	2197
sand	2202
shale	2230
shals & lime	2336
shale	2385
lime, Howard	2442
shale	2456
sand, Severy	2462
shale	2500
lime, Topeka	2520
lime & shale	2596
black shale	2602
lime & shale	2687
black shale	2690
lime	2787
black shale	2792
shale	2807
lime	2818
shale	2917
lime, brown	2922
shale	2950
lime	2974
oolitic, oil sat.	2978
lime	3087
shale	3096
lime & shale breaks	3242
shale	3261
lime	3297
shale	3304
amber chert	3307
shale, Simpson	3323
dolomite	3330
sand	3332
shale	3369
dolomite	3385
Total Depth	

DST 2960-3000' Op 60 min. Gas in
37 min. 658' gassy oily mud. 94' free
oil IP 1091#, FP 702#/20 min.

DST 3329-3355' (No blow) Op 20 min.
5 gal. Rotary mud FP 84#/20 min.

TOPS:	
Top Topeka	2503
Top Heebner	2790
Top Brown Lime	2919
Top Lansing	2950
Base Kansas City	3234
Top Sooy	3304
Top Simpson Shale	3307
Top Simpson Dolomite	3323
Top Arbuckle	3369

RECEIVED
STATE CORPORATION COMMISSION
APR 3 - 1972
CONSERVATION DIVISION
Wichita, Kansas