


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rice County. Sec. 4 Twp. 21-S Rge. 9-W (E) (W)  
Location as "NE/CNW/SW" or footage from lines NW NW SW  
Lease Owner Phoenix Drilling Corporation  
Lease Name Ross #1 Well No. 1  
Office Address 416 Union Center Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed December 26, 19 68  
Application for plugging filed December 26, 19 68  
Application for plugging approved December 26, 19 68  
Plugging commenced December 26, 19 68  
Plugging completed December 26, 19 68  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman, Box 180, Holyrood, Kansas 67450  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 235 feet. Set plug at 235 feet with 1/2 sx. hulls and 25 sx. cement through drill pipe. Heavy mud to 40 feet. Set plug at 40 feet with 10 sx. cement. 2 sx. in rat hole. Job completed at 5:30 P.M. 12-26-68.

4-10-69

RECEIVED  
STATE CORPORATION COMMISSION  
APR 10 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Phoenix Drilling Corporation  
Address 416 Union Center Building, Wichita, Kansas 67202


STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Jay C. Clark (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jay C. Clark  
Jay C. Clark  
416 Union Center Building, Wichita, Kansas  
(Address)

Subscribed and Sworn to before me this 8th day of January, 19 69

Phyllis Gillen  
Phyllis Gillen, Notary Public.

August 30, 1969



DRILLERS LOG

COMPANY: Phoenix Drilling Corporation  
 CONTRACTOR: Company tools  
 LEASE NAME: Ross No. 1  
 LOCATION: NW NW SW, Section 4-21S-9W  
 Rice County, Kansas  
 ELEVATION: 1680' G.L. - 1685' K.B.  
 SURFACE CASING: 243 ft. of new 20# 8-5/8"  
 COMMENCED: December 17, 1968  
 COMPLETED: December 26, 1968  
 ROTARY TOTAL DEPTH: 2983 feet

<u>FORMATION</u>	<u>DEPTH</u>
Surface Soil-Sand	300
Redbed	700
Shale-Shells	1460
Shale	1529
Lime	1850
Lime-Shale	1965
Shale	2005
Shale-Lime	2110
Shale-Lime Streaks	2240
Shale-Lime Shells	2505
Lime-Shale	2530
Lime	2625
Lime-Shale	2791
Shale-Lime	2855
Lime-Shale	2983
RTD	2983

Spudded at 7:00 A.M. 12-17-68.  
 Drilled 12-1/4" surface hole to 243 feet.  
 Ran 243 feet of 8-5/8" surface pipe.  
 Cemented with 200 sx. Common Sunset  
 cement, 2% CC. Plug down at 6:00 P.M.  
 12-17-68. Cement circulated.  
 DST #1: 2957-2983 feet  
 No Electric Log run.  
 Plugged hole at 5:30 P.M.-12-26-68

<u>SAMPLE TOPS</u>	<u>DEPTH</u>	<u>DATUM</u>
Topeka	2498	- 813
Heebner	2783	-1098
Toronto	2805	-1120
Douglas	2814	-1129
Brown Lime	2917	-1232
Lansing	2950	-1265
Rotary Total Depth	2983	-1298

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 10 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 ) ss:  
 COUNTY OF SEDGWICK )

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

Jay C. Clark  
 Jay C. Clark

Subscribed and sworn to before me this 8th day of January, 1969.

Phyllis Gillen  
 Notary Public Phyllis Gillen

My commission expires: 8-30-69

