

10-15

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

2-090546

API Number: 15-11304587

SW SW SE SECTION 29 TWP 21 RANGE 01W

OPERATOR LICENSE #5663 330 FEET FROM S SECTION LINE
OPERATOR HESS OIL COMPANY 2310 FEET FROM E SECTION LINE
NAME 3 P.O. BOX 1009
ADDRESS MCPHERSON, KS 67460

LEASE NAME GRABER #1
COUNTY MCPHERSON
WELL TOTAL DEPTH 3331' 108.26
PIPE 7" @ 3314'
SURFACE CASING 8 5/8" @ 3107'
CONDUCTOR 16" @ 129'

ABANDONED OIL WELL ☒ GAS WELL ☐ INPUT WELL ☐ SWD ☐ D&A ☐

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: D & R WELL SERVICE

ADDRESS: P.O. BOX 1009, MCPHERSON, KS 67460 LICENSE: 5663

COMPANY TO PLUG AT: HOUR: 8:00 DAY: 8 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM: JAMIE HESS

COMPANY NAME: HESS OIL COMPANY PHONE:

WERE: SAND TO 2850'. CAP WITH 7 SACKS CEMENT. RIP PIPE FOR RECOVERY.

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 21 1998

CONSERVATION DIVISION
WICHITA, KS

PLUGGING PROPOSAL RECEIVED BY: RALPH TITTEL

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ☐ PART ☒ NONE ☐

COMPLETED: HOUR: 15:00 DAY: 15 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT: SANDED TO 2850'. CAPPED WITH 7 SACKS CEMENT. RIPPED 7" AT 450' AND PULLED
SAME RIPPED HOLES INTO 8 5/8" @ 400'. COULDN'T PULL SAME. RAN 2 1/2" TUBING TO 400'. SPOTTED 250
SACKS CEMENT THROUGH 2 1/2" TUBING. CIRCULATED ON BACK SIDE. CEMENT LEFT OVERNIGHT. SETTLED TO 130'
BAIL X DRY AND FILL WITH READY MIX INSIDE AND OUTSIDE.

REMARKS: UNITED CEMENTING - 250 SACKS 60/40 POZ, 4% GEL. PLENERT CONCRETE 3 YARDS REDIMIX

I DID OBSERVE THIS PLUGGING.

Ralph Tittel
RALPH TITTEL

FORM CP-2/3
REV. 3/90

OCT 21 1998

60150