

5 030191

15.113.04599.0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drd 8-10-37  
NE/4, SEC. 29, T. 21 S, R. 1 W  
\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5663

Lease Name J.A. Hetzke, Well # 8

Operator: Hess Oil Co.

County McPherson 108.10

Name & Address P.O. Box 905

Well Total Depth 3326 feet

2080 E. Kansas

Conductor Pipe: Size \_\_\_\_\_ feet

McPherson, Ks 67460

Surface Casing: Size 10 3/4 feet 139 w/ 150 rf

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated 7" @ 3308' w/ 300 rf

Plugging Contractor Co tools License Number 5663

Address \_\_\_\_\_

Company to plug at: Hour: 9 Am Day: 7 Month: Nov Year: 19 85

Plugging proposal received from Jim Hess

(company name) Hess Oil Co. (phone) 316 241-4640

were: Run measuring line find T.D. plug Bottom off with sand to 50' above Perf. Cap w/ 600 cement.

Run 300' tubing Circulate cement to surface inside 7" + outside. No pipe recovery.

Plugging Proposal Received by Merlan W. Munn  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4 pm Day: 7 Month: Nov Year: 19 85

ACTUAL PLUGGING REPORT Found hole to be Bridged in 7" casing @ 619' fluid @ 503'. Tried to wash out Bridge, without success. Cemented 7" w/ 2" tubing @ 307' to surface. Ran 1" tubing between 10 3/4" and 7" casings, circulated cement to surface, used approx 500 rf inside 7" and 1500 rf between casings.

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-21-85

INV. NO. 11097

RECEIVED  
STATE CORPORATION COMMISSION

NOV 19 1985

Signed Merlan W. Munn  
(TECHNICIAN)