

15.113.30243.0001  
2-010072

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 207B  
Wichita, Kansas 67202

API NUMBER: 4/30/38

NW NE SW, SECTION 29 TOWNSHIP 21 RANGE 1W

OPERATOR LICENSE # 5663 2310 FEET FROM S SECTION LINE  
3670 FEET FROM E SECTION LINE

OPERATOR HESS OIL COMPANY  
NAME & P O BOX 1009  
ADDRESS MCPHERSON KS 67460

LEASE NAME: J C GOERING #7

COUNTY: MCPHERSON 107.41

WELL TOTAL DEPTH: 3305' (2916')

PIPE: \_\_\_\_\_

SURFACE CASING: 10" @ 158'

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SMD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: HESS OIL COMPANY  
ADDRESS: P O BOX 1009, MCPHERSON KS 67460 LICENSE: 5663

COMPANY TO PLUG AT: HOUR: 14:00 DAY: 28 MONTH: 2 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: BRYAN HESS

COMPANY NAME: HESS OIL COMPANY PHONE: 316-241-4640

WERE: TOP BIRDGE PLUG @ 2916' W/10 SX CMT - RIP PIPE @ 380'  
- BUILD BRIDGE @ 380' & FILL W/SLURRY MIX TO SURF

7" CSG @ 3252' - PERFS @ 2905'-2911' AND 2924'-2928'

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( \_\_\_\_\_ ) PART (  ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 15:00 DAY: 28 MONTH: 2 YEAR: 1995

ACTUAL PLUGGING REPORT:

TOPPED BRIDGE PLUG @ 2916' W/10 SX CMT - RIPPED PIPE  
@ 412' - BUILT BRIDGE @ 380' - FILLED HOLE W/7-1/2 YDS  
SLURRY MIX TO SURF - SLURRY MIX WAS 9408 LBS CMT, 6279  
LBS FLY ASH, 754 GAL WTR AND 14 LBS A.E.

REMARKS: USED SLURRY MIX BY MCPHERSON CONCRETE PROD #4

I DID OBSERVE THIS PLUGGING.

DATE 3-28-95  
INV. NO. 42452

Michael R. Wilson  
Michael R. Wilson (AGENT)

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 27 1995

CONSERVATION DIVISION  
WICHITA, KS  
REV. 3/90