

7-20

2 100513

API NUMBER 15- 1937 E-01.911

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE NW, SEC. 29, T 21 S, R 1 WXR

4950 feet from N/S section line

2970 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5663

Lease Name Huxman Well # 2

Operator: Hess Oil Company

County McPherson 108.00

Name & Address P. O. Box 1009

Well Total Depth 3323 feet

McPherson, KS 67460

Conductor Pipe: Size 7" feet 3275'/300 sx

316-241-4640

Surface Casing: Size 10-3/4 feet 137'/150 sx

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated open hole 3275'-3323'

Plugging Contractor Hess Oil Company License Number 5663

Address P.O. Box 1009 McPherson KS

Company to plug at: Hour: 5:00p Day: 20 Month: 7 Year: 19 89

Plugging proposal received from _____

(company name) _____ (phone) _____

work: Sand 50' above open hole 10 sx cement - shoot & pull pipe - fill to
surface w/slurry mix from 250'

Plugging Proposal Received by WK
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 6:00p Day: 20 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT Plugged off at 500' with tubing - put 5 sx cement at
500' - filled outside 7" with 1" from 246' - filled inside w/1-1/4" from
260' with 8-1/4 yds of slurry mix

Remarks: Plennert

INVOICED (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 7-31-89

Signed J.L. Sanderson
(TECHNICIAN)

INV. NO. 25459

OCT 04 1989

Rec'd Ke
JUL 28 1989