

6-26

5 030507

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- E-01,911 Dr1g 1937
NW, SEC. 29, T 21 S, R 1 W/EX
4950 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5663

Lease Name Huxman Well # 2
County McPherson 108.00

Operator: Hess Oil Company
Name & Address P. O. Box 1009
McPherson, KS 67460

Well Total Depth 3323 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10-3/4 feet 137'/150 sx

Abandoned Oil Well _____ Gas Well _____ Input Well x SWD Well x D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Company Tools License Number _____
Address _____

Company to plug at: Hour: _____ pm Day: 21 Month: 6 Year: 19 89

Plugging proposal received from Bryan Hess

(company name) Hess Oil Company (phone) 316-241-4640

were: 7" @ 3298' - 2-1/2" fiberglass tubing parted 19-1/2 joints from surface -
unable to fish @ 563' - would not take fluid down hole - place 5 sx cement - check
fillup - recover available pipe - cement with tubing 250' plus inside & outside of
7" casing to surface

Plugging Proposal Received by Ralph Tittel
(TECHNICIAN)

Plugging Operations attended by Agent?: All ✓ Part _____ None _____

Operations Completed: Hour: 12:30 Day: 26 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT Placed 12 gals crushed rock on plugged tubing @ 563' -
followed w/5 sx cement - top @ 526' - ran 1" tubing between 10-3/4" & 7"
casing to 256' - cemented w/approx 85 sx to surface - ran 1-1/2" tubing in
7" casing 232' - cemented to surface.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS

JUL 13 1989

Plenert Construction #451-#453

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOLVED

and observe this plugging.

DATE 7-18-89

INV. NO. 25361

W

Signed Merlan L...uh
(TECHNICIAN)