

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

DEC 27 1990

CONSERVATION DIVISION
Wichita, Kansas

2-060231

15.113.02050.0000

API NUMBER: 12/24/41

C W/2 SW NE, SECTION 16 TOWNSHIP 21 RANGE 3W

OPERATOR LICENSE # 5572

FEET FROM S SECTION LINE

FEET FROM E SECTION LINE

OPERATOR Law Production, Inc.

NAME & Box 129

ADDRESS McPherson, KS 67460

LEASE NAME: P. A. Koehn #5

COUNTY: McPherson

WELL TOTAL DEPTH: 3380' 109.85

CONDUCTOR PIPE: 4-1/2" @ 3332'/150 sx

SURFACE CASING: 8-5/8" @ 162'

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: Kelso Casing Pulling, Inc.

ADDRESS: P. O. Box 347, Chase, KS 67524

LICENSE: 6050

COMPANY TO PLUG AT: HOUR: am DAY: 19 MONTH: 12 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Mike Kelso

COMPANY NAME: Kelso Casing Pulling, Inc.

PHONE: 316-241-3460

WERE: Sand to 3300' cap w/4 sx cmt or pump 20 sx cmt -
displace w/40 bbls water - shoot @ 450' - if loose,
circ cmt - if not loose, pump 50 sx cmt - displace to
250' - shoot at 200' - circ cmt.

PLUGGING PROPOSAL RECEIVED BY: District #2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART () NONE ()

COMPLETED: HOUR: 3:00p DAY: 19 MONTH: 12 YEAR: 1990

ACTUAL PLUGGING REPORT:

Couldn't get down to 3300' - pumped 20 sx cmt -
displaced w/40 bbls water (2465') - on slight vac. -
shot at 450' - not loose - pumped 50 sx cmt -
displacing cmt to 250' (250'-1000' cmt) - shot @ 200' -
not loose - shot @ 168' - not loose - tagged at 6' on
outside and 174' on inside of 4-1/2" - pumped 30 sx cmt
into 4-1/2" to surface.

REMARKS: Halliburton Services #060915 40/60 poz 2% gel

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE JAN 09 1991

INV. NO. 30432

12-19

R. Phil Worley

R. Phil Worley

(AGENT)

FORM CP-2/3
REV. 3/90