

1 030512

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,209.0000

SE NW NE, SEC. 19, T 21 S, R 23 W/X

4300 feet from S section line

1930 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9911

Lease Name Gumbir Well # 3

Operator: Har-Ken Oil Company

County Hodgeman 15/13

Name & Address 7333 E. 22nd Street, # 6

Well Total Depth 4650 Mississippi feet

Wichita, KS 67226

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 520

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Co. License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 1:00 pm Day: 9 Month: September Year: 19 85

Plugging proposal received from Albert Augustine

(company name) Murfin (phone) 316-267-3241

to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1605-1620' Elevation 2344

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 50 sx cement

3rd plug 30' out of the surface pipe with 50 sx cement solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:00 pm Day: 9 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1620' with 50 sx cement, 2nd plug at 1260' with 50 sx

cement, 3rd plug at 550' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(if additional description is necessary, use BACK of this form.)

INVOICED

not) observe this plugging

SEP 17 1985

RECEIVED STATE CORPORATION COMMISSION Signed

Paul A. Luthi (TECHNICIAN)

DATE

INV. NO. 10125

OCT 09 1985

SEP 16 1985

DEC 12 1985

AMENDED
CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

Collection
8-2885
CARD MUST BE SIGNED

Starting Date: August 12, 1985
month day year

API Number 15- 083-21,209-0000
SE NW NE Sec 19 21 23 East
(location) West

OPERATOR: License # 9911
Name Har-Ken Oil Company
Address 7333 E. 22nd St., #6
City/State/Zip Wichita, KS 67226
Contact Person Donald M. Brown
Phone 316-684-1146

4300 Ft North from Southeast Corner of Section
1930 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 6033
Name Murfin Drilling Co.
City/State Wichita, KS

Nearest lease or unit boundary line 710 feet.
County Hodgeman
Lease Name Gumbir Well# 3
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water 500 feet
Lowest usable water formation Dakota
Depth to Bottom of usable water 500 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 520 feet
Conductor pipe if any required feet
Ground surface elevation 2344 feet MSL
This Authorization Expires 2-6-86
Approved By 8-6-85

If OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 4650 feet
Projected Formation at TD Mississippian
Expected Producing Formations Mississippian

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications. *was: COWNE 4610 FSL 1980 FEL*

Date 8-6-85 Signature of Operator or Agent Donald M. Brown Title Local Rep.

Form C-1 424

RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1985

CONSERVATION DIVISION
Wichita, Kansas