

1090345

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,190-0000

C NE SE, SEC. 19, T 21 S, R 23 W/E

1980 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9911

Lease Name Gumbir Well # 2

Operator: Har-Ken Oil Company

County Hodgeman 151.13

Name & Address 7333 E. 22nd Street, # 6

Well Total Depth 4650 feet

Wichita, KS 67226

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 526

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829

Address Box 18611, Wichita, KS 67207

Company to plug at: Hour: 7:15 pm Day: 23 Month: March Year: 19 85

Plugging proposal received from Mark Guinn

(company name) Aldebaran (phone) 316-685-5372

to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1630' with 50 sx cement

2nd plug at 650' with 50 sx cement

solid bridge

3rd plug hulls - plug at 40' - cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Robert B. Tarbutton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:15 pm Day: 23 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1630' with 50 sx cement, 2nd plug to circulate

rat hole with 15 sx cement, 3rd plug to circulate mouse hole with 10 sx cement.

RECEIVED

WELL TO BE PUT ON T/A FOR CONSTRUCTION OF DISPOSAL BY June 1985 STATE CORPORATION COMMISSION

MAY 28 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

(Also, do not) observe this plugging.

INVOICED

6-8-85

DATE

8365

INV. NO.

Signed R B Tarbutton (TECHNICIAN)

15.083.21190.0000

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: March 15, 1985
month day year 4:00

API Number 15- 083-21,190

OPERATOR: License # 9911
Name Har-Ken Oil Company
Address 7333 E. 22nd St. #6
City/State/Zip Wichita, KS 67226
Contact Person Donald M. Brown
Phone 316-684-1146

C NE SE ... Sec 19 Twp 21 S. Rge 23 East West
(location)

1980 Ft North from Southeast Corner of Section
660 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5829
Name Aldebaran Drilling Co., Inc.
City/State Wichita, KS

Nearest lease or unit boundary line 660 feet.
County Hodgeman
Lease Name Gumbir Well# 2
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 DWWO Expl Wildcat Cable

Depth to Bottom of fresh water 500 feet
Lowest usable water formation Dakota
Depth to Bottom of usable water 500 feet

If DWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Surface pipe by Alternate: 1 2
Surface pipe to be set 520 526 feet
Conductor pipe if any required feet
Ground surface elevation feet MSL

Projected Total Depth 4650 feet
Projected Formation at TD Mississippian
Expected Producing Formations Cong. & Miss.

This Authorization Expires 9-13-85
Approved By 3-13-85 KC

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

te 3-13-85 Signature of Operator or Agent Donald M. Brown Title Local Rep. 210 MHC/KOHE 3-13-85

Form C-1 4/84

move in 3-17-85 set 500' 8 5/8

RECEIVED
STATE CORPORATION COMMISSION

MAY 28 1985

CONSERVATION DIVISION
Wichita, Kansas

1 090386

Greg Hartsegh

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,190-0000
C NE SE 1/4, SEC. 19, T 21 S, R 23 W XX
1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9911
Operator: HAR-KEN OIL COMPANY
Name & Address: Box 626
2101-81 Calhoun Road
Owensboro, KY 42302

Lease Name GUMBIR Well # 2
County HODGEMAN 151.78
Well Total Depth 4670(MISS) feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8" feet 518

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Well Service, Inc. License Number 6454
Address Box 384, Ness City, KS 67560

Company to plug at: Hour: 9:30 a.m. Day: 15 Month: Oct. Year: 19 85

Plugging proposal received from Dargen Settles
(company name) HAR-KEN Oil Co. Area 502- (phone) 926-2282

were: tag the top of a previously set plug in the anhydrite and then set
a 70 sack cement plug at 650 feet and a 10 sack cement plug at 40 feet to
the surface.

Plugging Proposal Received by Don Ubel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:00 a.m. Day: 15 Month: Oct. Year: 1985

ACTUAL PLUGGING REPORT

A plug was placed at 1630 feet with 50 sacks cement on March 23, 1985 and the well was shut in by putting a swedge and valve on the 8 5/8" surface pipe. The hole was re-entered with tubing and the anhydrite plug was tagged at 1388 feet. Then the hole was loaded with mud and a plug was spotted at 670 feet with 70 sacks cement. Tubing was then pulled out of the hole and waited on cement to set. Ran back in the hole with tubing and tagged the top of the plug at 430 feet. Pulled tubing up to 40 feet

Remarks: and set a 10 sack cement plug to surface. Haliburton cemented with 60/40 Pozmix, (If additional description is necessary, use BACK of this form.) using 6% gel.

INVOICED

DATE 12-9-85

INV. NO. 11335

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1985

Signed Robert Barburton
(TECHNICIAN)