

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-21175-00-00  
Spot: CSWNE Sec/Twnshp/Rge: 19-21S-23W  
3300 feet from S Section Line, 1980 feet from E Section Line  
Lease/Unit Name: GUMBIR Well Number: 1  
County: HODGEMAN Total Vertical Depth: 4567 feet

Operator License No.: 31627  
Op Name: WHITETAIL CRUDE, INC  
Address: 201 WASH PO BOX 544  
NESS, KS 67560

12/22

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 570 350 SX CMT  
Production: Size 4.5 feet: 4564 230 SX CMT  
Liner: Size \_\_\_\_\_ feet:

148.43

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/22/2000 2:30 PM

Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: MIKE J. FRITZLER Company: WHITETAIL CRUDE Phone: (785) 798-3641

Proposed Plugging Method: TIE ONTO 4-1/2 & PUMP CMT & HULLS TO PLUG THE OPEN HOLE WITH 20 SX CMT. & GEL SPACER TO 2000. FILL PIPE AND CHECK BACKSIDE OF 8-5/8.

Plugging Proposal Received By: MICHAEL MAIER  
Date/Time Plugging Completed: 12/22/2000 3:30 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

OPEN HOLE. DV AT 1550' WITH 325 SX CMT AND CIRCULATED TO SURFACE. PUMPED 50 SX CMT AND 300# HULLS. GEL TO 1550' THEN MIXED 80 SX CMT. MAXIMUM PRESSURE 1000#. SHUT IN AT 500#. TIED ONTO BACKSIDE AND IT PEASURED TO 500# AND HELD.

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 05 2001

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

INVOICED

Signed

*Michael Maier*  
(TECHNICIAN)

DATE

1/8/01

JAN 02 2001

NOV. 2001

200106248

Form 5273

*MP*