

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

12-6

API NUMBER: 15-113-20,459-0000

NW NW SE, SECTION 35 TOWNSHIP 21 RANGE 2W

OPERATOR LICENSE # 5172 2310 FEET FROM S SECTION LINE
OPERATOR SCHULZ OIL & GAS INC. 2310 FEET FROM E SECTION LINE
NAME & P.O. BOX 273
ADDRESS CANTON, KS 67428

LEASE NAME: VOGT #1
COUNTY: McPHERSON
WELL TOTAL DEPTH: 3154' 102.50
PIPE: _____
SURFACE CASING: 8 5/8" @ 132'

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: QUALITY WELL SERVICE INC
ADDRESS: 249 EAST BETH DRIVE, STERLING, KS 67579 LICENSE: 31925

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 5 MONTH: 12 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: MITCH SCHULZ
COMPANY NAME: SCHULZ OIL & GAS INC. PHONE: (316) 628-4431
WERE: SAND TO 3015' AND CAP WITH 4 SACKS OF CEMENT. SHOOT PIPE OFF AND PULL SAME. RUN TUBING TO 400' AND CIRCULATE CEMENT TO SURFACE.

4 1/2" CASING AT 3151'
PERFORATIONS AT 3067' TO 3082'

PLUGGING PROPOSAL RECEIVED BY: JERRY CLARK

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { _____ } PART { X } NONE { _____ }

COMPLETED: HOUR: 10:00 DAY: 6 MONTH: 12 YEAR: 1996

ACTUAL PLUGGING REPORT: SANDED 3015' AND TOPPED WITH 4 SACKS OF CEMENT. SHOT PIPE OFF AT 1913' AND PULLED SAME. RAN 2 3/8" TUBING TO 403' AND PUMPED 275 SACKS OF CEMENT. CEMENT DID NOT CIRCULATE TO SURFACE. WAITED THEN TAGGED CEMENT WITH TUBING AT 185'. CIRCULATED 110 SACKS OF CEMENT TO THE SURFACE.
RETRIEVED 1913' OF 4 1/2" CASING TOTAL CEMENT USED: 385 SACKS

REMARKS: 60/40 POZ 2% GEL UNITED #3225 & #3226

RECEIVED
KANSAS CORPORATION COMMISSION
INVOICED
DATE JAN 03 1997 DEC 16 1996
INV. NO. 47245
CONSERVATION DIVISION
WICHITA, KS
FEB 17 1997

I DID OBSERVE THIS PLUGGING.
Michael R Wilson
MICHAEL WILSON