

To: 1 070916
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5701

Operator: National Oil Company

Name & Address

P.O. Box 399

Garden City, KS 67846-0399

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor National Oil Company License Number 5701

Address P.O. Box 399, Garden City, KS 67846-0399

Company to plug at: Hour: 12:10 p.m. Day: 13 Month: 2 Year: 19 91

Plugging proposal received from Dean Ives

(Company name) National Oil Company (phone) 316-275-2963

Work: 5 1/2" at 4428' w/125 sx cement, Open hole 4428-37', Hole in casing was squeezed at 961' with 125 sx cement in 1980.

1st plug spot 20 sx cement at 4200',

2nd plug pump through tubing 20 sx cement at 1550',

3rd plug pull tubing to 950' and circulate cement to surface.

Check backside.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4 p.m. Day: 13 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug spotted 20 sx cement at 4200',

2nd plug pumped through tubing 20 sx cement at 1550',

3rd plug pulled tubing to 950' and circulate cement to surface with 106 sx cement.

4th plug pulled tubing and topped off with 33 sx cement.

Backside would not take.

Remarks: Used 65/35 Pozmix 6% gel by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED (Plugging) observe this plugging.

DATE 2-27-91

INV. NO. 30925

2-13

MAY 03 1991

Signed Dan Goodrow (TECHNICIAN)