

1060155

TO: STATE CORPORATION COMMISSION

4-13

API NUMBER 15-083-20,394.0000
C NW NE SEC. 24, T 21 S, R 25 W

CONSERVATION DIVISION - PLUGGING SECTION 4620 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME WITMAN WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY HODGEMAN 145.54

OPERATOR LICENSE # 5131

WELL TOTAL DEPTH 4478 FEET

OPERATOR: THUNDERBIRD DRILLING, INC PRODUCTION CSG: SIZE 5 1/2" @ 4461' WITH 100 SX

NAME AND PO BOX 97 SURFACE CASING: SIZE 8 5/8" @ 325' WITH SX

ADDRESS ELLINWOOD, KS 67526

ABANDONED OIL WELL X GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 10:40 AM DAY: 13 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT OPEN HOLE

1ST PLUG SET CIBP AT 4320' AND PLUG WITH 25 SX CEMENT.

2ND PLUG RUN TUBING TO 800' AND USE 175 SX CEMENT WITH 500# HULLS AND CIRCULATE CEMENT.

3RD PLUG PULL TUBING TO 60' THEN MIX 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:45 AM DAY: 13 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SET CIBP AT 4320' WITH 25 SX CEMENT.

2ND PLUG RUN TUBING TO 800' AND USED 175 SX CEMENT WITH 500# HULLS AND CIRCULATED CEMENT.

3RD PLUG PULLED TUBING TO 60' THEN MIXED 10 SX CEMENT. HOLE STAYED FULL.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1650' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED

RECEIVED STATE CORPORATION COMMISSION

FIELD OBSERVER THIS PLUGGING.

SIGNED Michael J Maier (TECHNICIAN) FORM CP-2/3

DATE 4-30-99

APR 28 1999

INV. NO. 60911

CONSERVATION DIVISION Wichita Kansas