

1040975 6-22  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION App.  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-093-21,455.0000  
SE SE SW, SEC. 19, T 21 S, R 38 W/EX  
600 feet from S section line  
2980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952  
Operator: Amoco Production Company  
Name:  
Address: P.O. Box 800  
Denver, CO 80201

Lease Name Wyatt E Well # 1-19  
County Kearny  
Well Total Depth 5450 177.13 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 1092

Abandoned Oil Well Gas Well Input Well SWD Well D&A X  
Other well as hereinafter indicated

Plugging Contractor Cheyenne Drilling License Number 5382  
Address P.O. Box 916, Garden City, KS 67846

Company to plug at: Hour: 6:39 a.m. Day: 22 Month: 6 Year: 19 95

Plugging proposal received from Duane  
(company name) Cheyenne Drilling (phone) 316-277-2062

Work: to fill hole with heavy mud and spot cement through drill pipe  
1st plug at Hugoton/Council Grove with 100 sx cement,  
2nd plug at 2045' with 50 sx cement, 3rd plug at 1120' with 50 sx cement,  
4th plug at 560' with 50 sx cement, 5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10  
sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:10 a.m. Day: 22 Month: 6 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug at 3400' with 100' sx cement,  
2nd plug at 2052' with 50 sx cement, 3rd plug at 1122' with 50 sx cement,  
4th plug at 560' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 6-30-95  
OBSERVE THIS PLUGGING.

DATE 6-30-95  
INV. NO. 43014  
6-22

Signed [Signature]  
(TECHNICIAN)

STATE CORPORATION COMMISSION  
RECEIVED  
JUN 26 1995

