

1080245

TO: STATE CORPORATION COMMISSION

4-9

API NUMBER 15-093-21,638.0000
NW NW NW SEC. 19, T 21 S, R 38 W

CONSERVATION DIVISION - PLUGGING SECTION 490 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MAUNE WELL # 4-19

TECHNICIAN'S PLUGGING REPORT COUNTY KEARNY

OPERATOR LICENSE # 32059 WELL TOTAL DEPTH 5400 FEET

OPERATOR: GULF PRODUCTION CORP. PRODUCTION CSG: SIZE " FEET

NAME AND 9701 N BROADWAY EXT SURFACE CASING: SIZE 8 5/8" @ 360' WITH SX

ADDRESS OKLAHOMA CITY, OK 73114

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MURFIN DRILLING COMPANY, INC LICENSE NUMBER 30606

ADDRESS 250 N WATER, SUITE 300, WICHITA, KS 67202

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 09 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM GUS

(COMPANY NAME) MURFIN DRILLING COMPANY, INC (PHONE) 316-267-3241

WEPE:

1ST PLUG AT 2095 WITH 50 SX CEMENT. 2ND PLUG AT 1188' WITH 80 SX CEMENT.

3RD PLUG AT 375' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:50 PM DAY: 09 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 2095 WITH 50 SX CEMENT. 2ND PLUG AT 1188' WITH 80 SX CEMENT.

3RD PLUG AT 375' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
APR 22 1999
CONSERVATION DIVISION
Wichita, Kansas

REMARKS: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY HALLIBURTON
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED
WITH OBSERVE THIS PLUGGING.

DATE APR 23 1999

SIGNED [Signature] (TECHNICIAN) FORM CP-2/3 [Signature]

INV. NO. 60880