

To: 1 060192  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 093-21,247-0000  
SE NW NE, SEC. 22, T 21 S, R 38 W/2  
4290 feet from S section 11n  
1650 feet from E section 11n

TECHNICIAN'S PLUGGING REPORT

Operator License # 5030  
Operator: Vess Oil Corporation  
Name & Address: 8100 E. 22nd St. N, Bldg. 300  
Wichita, KS 67226

Lease Name Maune Well # 1-22  
County Kearny  
Well Total Depth 4900 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 475

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Company License Number 30606  
Address E. Highway 24, Box 130, Hill City, KS

Company to plug at: Hour: 1:30 p.m. Day: 11 Month: 10 Year: 1993  
Mike Stanton

Plugging proposal received from \_\_\_\_\_  
(company name) Murfin Drilling Co. (phone) 913-674-2103

were: 4 1/2" at 4134' w/770 sx cement, PBSD 4073', Perfs at 4029-35'.  
1st plug set CIBP at 3980' and dump 2 sx cement on top,  
2nd plug at 1200' with 50 sx cement,  
3rd plug at 750' with 50 sx cement,  
4th plug at 500' with 40 sx cement. 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X None \_\_\_\_\_  
Operations Completed: Hour: 4:30 p.m. Day: 11 Month: 10 Year: 1993

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3979' with 2 sx cement on top,  
2nd plug at 1200' with 50 sx cement,  
3rd plug at 850' with 50 sx cement,  
4th plug at 500' with 50 sx cement,  
5th plug at 40' with 10 sx cement,

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 29 1996

CONSERVATION DIVISION  
WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1728' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

1 (did / did not) observe this plugging.

Signed Cam Mound  
(TECHNICIAN)