

To: 1 090249 1-28
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-093-21,249.0000 137R
150' SW of
N/2 N/2 SW, SEC. 15, T 21 S, R 38 WEX

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113
Operator: Landmark Oil Exploration, Inc.
Name:
Address 250 N. Water, Ste. 308
Wichita, KS 67202

2204 feet from S section line
1174 feet from WEX section line
Lease Name McCormick Well # 1-15
County Kearny
Well Total Depth 4900 159.25 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 470

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company, Inc. License Number 30606
Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 12:30 a.m. Day: 28 Month: 1 Year: 19 93

Plugging proposal received from Rodney Farr
(company name) Murfin Drilling Co. (phone) 316-267-3241

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2176'
1st plug at 3000' with 100 sx cement, 2nd plug at 2180' with 50 sx cement,
3rd plug at 1180' with 80 sx cement, 4th plug at 700' with 40 sx cement,
5th plug at 480' with 50 sx cement, 6th plug at 40' with 10 sx cement,
7th plug to circulate rathole with 15 sx cement, 8th plug to circulate mousehole with 10 sx
cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)


Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5 a.m. Day: 28 Month: 1 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 3075' with 100 sx cement,
2nd plug at 2180' with 50 sx cement, 3rd plug at 1180' with 80 sx cement,
4th plug at 700' with 40 sx cement,
5th plug at 480' with 50 sx cement, 6th plug at 40' with 10 sx cement,
7th plug to circulate rathole with 15 sx cement,
8th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did not) observe this plugging.
DATE 2-18-93
INV. NO. 37383
1-28

Signed 
(TECHNICIAN)

EFFECTIVE DATE: 1-11-93
DISTRICT 1
SEAL Yes X No

15.093.21249.0000

FORM A
FORM A
ALL BLANKS MA

State of Kansas
NOTICE OF INTENTION TO DRILL 093-21,249

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date: January 7 1993 150' SW N/2 SW Sec 15 Twp 21-S Rg 38-W

OPERATOR: License # 06113
Name: Landmark Oil Exploration, Inc.
Address: 250 N. Water, Suite 308
City/State/Zip: Wichita, Kansas 67202
Contact Person: Jeff Wood
Phone: (316) 265-8181

2204 feet from South/WEST line of Sect.
1174 feet from WEST/West line of Section
IS SECTION XX REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Kearny
Lease Name: McCormick Well #: #1-15
Field Name: Unnamed

CONTRACTOR: License # 30606
Name: Murfin Drilling Co., Inc.

Is this a Propped/Spaced Field? yes XX no
Target Formation(s): LKC; Morrow
Nearest lease or unit boundary: 330
Ground Surface Elevation: Estimate 3347

Well Drilled For: Well Class: Type Equipment:
XX Oil ... Enh Rec ... Infield XX Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWWO ... Disposal XX Wildcat ... Cable
... Seismic; ... # of Holes ... Other

Water well within one-quarter mile: yes XX no
Public water supply well within one mile: yes XX no
Depth to bottom of fresh water: 170'
Depth to bottom of usable water: 1180'

If OWWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Surface Pipe by Alternate: 1 XX 2
Length of Surface Pipe Planned to be set: 450'
Length of Conductor pipe required: N/A
Projected Total Depth: 4950'
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
... well ... farm pond XX other

Directional, Deviated or Horizontal wellbore? yes XX no
If yes, true vertical depth:
Bottom Hole Location:

DER Permit #:
Will Cores be Taken?: yes XX no
If yes, proposed zone:
220' Alt. II Req.

AFFIDAVIT

Exp. 7/6/93

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-

Pusher Randy Jann
SPUD DATE 1-16-93 INIT. RR
LENGTH SURFACE PLANNED 450'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ 470' CONDUCTOR
ANHYDRITE T- B- 276' ELEVATION
TD 490' FORMATION
RAN PIPE @ DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ 3075 Ft. W/ SX
Hug./Council @ 3000 Ft. W/ 100 SX
Anhydrite Base @ 2180 Ft. W/ 250 SX
1/2 Base Anhy. @ 1180 Ft. W/ 80 SX
1/2, 1/2 Plug @ 200 Ft. W/ 40 SX
Bottom Surface @ 480 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL SX (Irr. Well Pond Hauling)
TECHNICIAN S.M. DATE
TYPE OF CEMENT 60/406 @ 1/4 FloSand
STARTING TIME 12:30 (AM/PM) DATE 1-28-93
COMPLETION TIME 5:00 (AM/PM) DATE 1-28-93
CEMENT COMPANY Allied