

1 050686

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,305.0000
100' north
SE NE NW, SEC. 31, T 21 S, R 11 W/EX
4390 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5339

Lease Name Mellies Well # 5

Operator: Bergman Oil Company

County Stafford 127.96

Name & Address

520 Union Center

Well Total Depth 3656 Arbuckle feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 260'

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Bergman Drilling, Inc. License Number 5659

Address 520 Union Center, Wichita, Ks 67202

Company to plug at: Hour: 6:00 am Day: 17 Month: November Year: 1985

Plugging proposal received from Dean Boechner

(company name) Bergman (phone) 316-267-5291

Elevation N/A

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 534

1st plug at 500' with 50 sx cement

2nd plug at 300' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:10 am Day: 17 Month: November Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 500' with 50 sx cement, 2nd plug at 300' with 40
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with
10 sx cement. 5th plug to circulate rat hole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED

NOV 25 1985

STATE CORPORATION COMMISSION
11-20-1983
NOV 20 1985

Signed Richard W. Lacey
(TECHNICIAN)

DATE

INV. NO. 11197

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84