

1070017

8-21

15.185.19161.0000

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Completion date 8/25/61

NW SW NW, SEC. 31, T 21 S, R 11 WXX
3630 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4058

Lease Name Mellies A Well # 1

Operator: American Warrior, Inc.

County Stafford 116, HS

Name & Address P.O. Box 399

Well Total Depth 3583 feet

Garden City, KS 67846

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 244

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Service License Number 6901

Address P.O. Box 231, Claflin, KS

Company to plug at: Hour: 1:15 p.m. Day: 21 Month: 8 Year: 19 97

Plugging proposal received from Kent Strube

(company name) D S & W Well Service (phone) 316-587-3361

Work: 5 1/2" at 3582' w/100 sx cement, PBTD 3580', Perfs at 3556-61'

1st plug sand back to 3500' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 21 Month: 8 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3500' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 440 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1684' of 5 1/2" casing.

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE 9-4-97

Signed [Signature] (TECHNICIAN)

INV. NO. 488.89