

To: 1 070016
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

8-21

API NUMBER 15-185-20,560.0000

SE NW NW, SEC. 31, T 21 S, R 11 W/E
4290 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 4058

Lease Name Mellies A Well # 2

Operator: American Warrior, Inc.

County Stafford 117.00

Name & Address P.O. Box 399

Well Total Depth 3600 feet

Garden City, KS 67846

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 255

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Service License Number 6901

Address P.O. Box 231, Claflin, KS

Company to plug at: Hour: 3:30 p.m. Day: 21 Month: 8 Year: 19 97

Plugging proposal received from Kent Strube

(company name) D S & W Well Service (phone) 316-587-3361

were: 5 1/2" at 3598' w/100 sx cement, PBTD 3580', Perfs at 3504-09, 3360-64'

1st plug sand back to 3310' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls and 225 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:15 p.m. Day: 21 Month: 8 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3310' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 400 lbs. hulls and 225 sx cement. Maximum pressure 800 psi and shut in 400 psi.

Remarks: Recovered 801' of 5 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton.

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE 8-4-97

INV. NO. 488.90

Signed [Signature] (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KS
8-21-97
RWL