

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Rush SEC. 1 TWP. 16 RGE. 20W E/W
Location as in quarters or footage from lines:
NE NW SE

Locate Well
correctly on above
Section Platt.

Lease Owner Edmiston Oil Co., Inc.
Lease Name Peifer #1 Well No. _____
Office Address 800 Vickers/KSB&T Bldg., Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 5/1/81
Plugging completed 6/5/81
Reason for abandonment of well or producing formation _____

RECEIVED
STATE CORPORATION COMMISSION

JUN - 9 1981

CONSERVATION DIVISION
Wichita, Kansas

Depleted
Was permission obtained from the Conservation Division's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ bottom T.D. 3719'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	1310'	None
				4 1/2"	3718'	2900'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in. Water flowing out of surface. Pushed wooden plug to 3300', sanded to 3250' and set 4 sacks cement. Loaded the hole with salt water. Pulled 22" stretch. Shot at 2900', worked pipe loose, and pulled a total of 70 joints. Plugged well with 4 sacks hulls, 10 sacks gel, plug and 140 sacks 50/50 pos 6% gel. Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of June, 19 81

My Commission expires: _____



Joan Kelso
Notary Public.

KANSAS DRILLERS LOG

COMPANY Ram Petroleum Corporation

SEC. 1 T. 16W R. 20W

FARM Pfeiffer NO. 1

LOC. NE NW SE

COUNTY Rush

ROTARY TOTAL DEPTH 3,719'
 COMM. July 30, 1980 COMP. August 11, 1980
 CONTRACTOR H-30, Inc. (Rig #2)
 ISSUED August 25, 1980

CASING

10 3/4"
 8 5/8" Set at 1,307' cemented w/500 sxs cement ELEVATION 2,094' K.B.
 5 1/2"
 4 1/2" Set at 3,718' cemented w/175 sxs cement

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale and Shells	730'
Sand	940'
Sand, Shale and Anhydrite	1,220'
Shale	1,295'
Anhydrite	1,335'
Shale	1,994'
Shale and Lime	2,465'
Lime and Shale	2,767'
Shale and Lime	2,960'
Lime	3,380'
Shale and Lime	3,430'
Lime	3,719'
Rotary Total Depth	3,719'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
 Dean Britting

State of Kansas)
) ss:
 County of Sedgwick)

Subscribed and Sworn to before me a Notary Public in and for said county and state this 25th day of August, 1980.



Elsie Willison
 Elsie Willison - Notary Public

My Commission Expires:
 July 25, 1982

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 10 1981
 CONSERVATION DIVISION
 Wichita, Kansas