

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rush County. Sec. 27 Twp. 18 Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines NE - SW - NW

Lease Owner Clark Knight Drilling Company

Lease Name Rodie "A" Well No. 4

Office Address Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 9-23 1958

Plugging completed 9-27 1958

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1049	None
				5 1/2	3623	3139.28

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with sand to 3570 and dumped 5 sks cement - mudded hole with fresh Jell mud to 300' - set 10' rock bridge - dumped 25 sks cement - mudded to 40' - set rock bridge - dumped 10 sks cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Company License # 236

Address Box 569 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

L. C. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

P.O. Box 162 - Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of October, 19 58

[Signature] (Ulanda Nichols) Notary Public.

My commission expires April 1, 1959

RECEIVED
STATE CORPORATION COMMISSION

OCT 4 1958

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 27 T. 18 R. 16 W
BOOK PAGE 131 LINE 13

WELL LOG

Clark Knight Drilling Co., Inc.

Lease - Rodie No. 1

NE SW NW

Sec. 27-18-16

Rush County, Kansas

Total Depth: 3,624' R.B.

Comm: 6-10-58 Comp: 6-22-58

Contractor: Ari-Kan Drilling Company

Rotary: 0-3,624'

Casing Records: 8 5/8" set @ 1,049' cemented w/ 450 sx Pozmix Cement w/2% GC --
circulated.

Figures indicate bottom of hole

Clay and post rock	35'
Shale and shell	450
Sand	540
Sandy strks and shale	675
Shale and shell	800
Red Bed	1034
Chalk	1040
Anhydrite	1060
Shale and shell	1880
Lime and shale	1930
Lime	2120
Lime and shale	2620
Shale and shell	2765
Lime and shale	3070
Lime	3218
Lime and shale	3255
Lime	3445
Chert and lime	3468
Lime	3580
Sand	3582
Core #1	3622
Core #2	3644
Ream core hole	3624
Total depth	3624'

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1958

CONSERVATION DIVISION PLUGGING
Wichita, Kansas FILE SEC. 27 T. 18 R. 16W
BOOK PAGE 131 LINE 13