


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rush County. Sec. 26 Twp. 18 Rge. 16 E (W)
Location as "NE/CNW $\frac{1}{2}$ /SW $\frac{1}{2}$ " or footage from lines
1001 N-SE/SW/NE
Lease Owner J. C. Musgrove, Inc.
Lease Name Schroeder Well No. 1
Office Address Box 611, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ October 31 1977
Plugging completed _____ November 7 1977
Reason for abandonment of well or producing formation _____

_____ depleted
If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3580'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	SIZE	PUT IN	PULLED OUT
		8 5/8"	973'	none
		4 1/2"	3579'	2766.21'

Describe in detail the manner in which well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand to 3500' and 4 sacks cement.
Shot pipe at 3100', 3000' and 2820'.
Pulled 73 joints 4 1/2" casing.
Plugged well with 1 sack hulls, 20 sacks gel, and 120 sacks 60/40 pozmix with 2% added gel.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.
Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
Box 698, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of November, 1977

My commission expires _____

Karen M. Morton
Notary Public.

DRILLERS' WELL LOG

DATE COMMENCED: August 10, 1977
 DATE COMPLETED: August 18, 1977

J. C. Musgrove, Inc.
 SCHROEDER # 1
 100' No. of SE SW NE
 Sec 26-T18-R16W
 Rush County, Kansas

ELEVATION: 1937 K.B.

0 - 25' Surface Soil, Clay
 25 - 333' Shale
 333 - 340' Hard Sand Streaks and Shale
 340 - 616' Shale and Sand
 616 - 810' Red Bed
 810 - 966' Red Bed, Shale
 966 - 994' Anhydrite
 994 - 1458' Shale
 1458 - 2910' Shale and Lime
 2910 - 3157' Lime
 3157 - 3161' Shale
 3161 - 3173' Lime and Shale
 3173 - 3193' Lime
 3193 - 3222' Shale
 3222 - 3237' Lime and Shale
 3237 - 3439' Lime
 3439 - 3483' Lime and Shale
 3483 - 3496' Shale, Lime, Chert & Sand
 3496 - 3580' Sand
 3580' RTD

FORMATION TOPS

Anhydrite	966
Topeka	2910
Heebner	3157
Toronto	3173
Douglas	3193
Brown Lime	3222
Kansas City	3237
Base K.C.	3439
Conglomerate	3483
Cong. Sand	3496
Reagan Sand	3527
RTD	3580

SURFACE PIPE:

Set used 8 5/8", 28# pipe at 973' w/225 sacks 50/50 Pozmix, 2% Gel, 3% cc and 200 sacks Common 2% Gel, 3% cc.

PRODUCTION PIPE:

Ran 4 1/2", 10 1/2# pipe at 3579' w/100 sacks 60/40 salt sat. Pozmix.

RECEIVED
 STATE CONSERVATION COMMISSION

NOV 01 1977

CONSERVATION DIVISION
 Wichita, Kansas

A F F I D A V I T

STATE OF KANSAS)
 COUNTY OF BARTON) ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 19th day of August, 1977.

Dorothy M. Hague
 Notary Public

My Commission Expires: April 11, 1978