

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

Locate well correctly on above
Section Plat

Rush County, Sec. 23 Twp. 18 Rge. 16 (E) (W) X
 Location as "NE/CNW/SE" or footage from lines C N - E - SE
 Lease Owner: Twin Western Resources, Inc.
 Lease Name: O. Schroeder Well No. #4
 Office Address: Suite 518, 200 East First St. Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole)
 Date well completed 19
 Application for plugging filed 19
 Application for plugging approved 19
 Plugging commenced 3-21-74 19
 Plugging completed 3-26-74 19
 Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Leo Massey
 Producing formation Depth to top Bottom Total Depth of Well 3558' Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3535'	Plug only
				8"	967'	
				12 1/2"	179'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3475', Mixed and ran 4 sacks cement thru dump bailer.
 Mudded hole to 350', set 15' rock bridge. Filled hole with 5 yards ready-mix


RECEIVED
 STATE CORPORATION COMMISSION
 MAR 28 1974
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor: Southwest Casing Pulling Co.
 Address: Box 364 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton 58.
 Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
 Box 364 Great Bend, Kansas (Address)

Subscribed and sworn to before me this 27 day of March, 1974



My commission expires 24 October 1976

Sidney D. Miller Notary Public.

COPY

MORGAN-FLYNN-COBY
O. Schroeder "B" No. 4.

S10.23 T.18 R.18 W
ONE SE

Total Depth. 3558'
Conn. 3-10-43 Comp. 3-0-45
Shot or Treated.
Contractor. Ayward Prod. Co.
Issued. 6-12-43

County. Rush



CASING:
12" 179' Con.
3" 967' Con.
5" 3535' Con.

Rotary Pump

Elevation.

Production. Pot. 138 B.

Figures Indicate Bottom of Formation.

clay & sand	0-50
sand	50
shale & red rock	250
shale & shells	375
shale	395
sand sft	425
sand hd & shale	520
sand sft	565
sand & shale	625
redrock	755
red bed	825
shale & red bed	930
red rock	984
anhydrite	995
red rock	1035
shale & red bed	1275
shale	1450
salt	1645
shells & shale	1970
shale & lime	1975
shale	2010
lime	2040
shale	2060
lime brkn	2105
lime & shale	2185
lime	2240
shale	2260
lime & shale brkn	2340
shale & shells	2550
lime & shale	2705
lime	2730
shale	2750
lime	2795
lime & shale	2840
shale	2990
lime	3075
lime brkn	3150
lime	3440
shale & lime	3465
lime	3510
lime & sand	3519
sand	3558
Total Depth.	

RECEIVED
STATE CORPORATION COMMISSION
JAN 25 1974
CONSERVATION DIVISION
Wichita, Kansas

Cored 3525-35 gas odor & oil stain
Cored 3535-40 gas odor & oil stain
3539 1/2-40 oil saturated
Cored 3540-46 oil saturated
Cored 3546-49 oil saturated