


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plot

Rush County, Sec. 23 Twp. 18 Rge. 16 (E) (W) X  
Location as "NE/CNWESW" or footage from lines C E/2 NW SE  
Lease Owner Twin Western Resources, Inc.  
Lease Name O. Schroeder Well No. #3  
Office Address 200 E. First St. Suite 518 Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 4-1-74 19  
Plugging completed 4-5-74 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well 3547' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	3548'	1203, 23'
				10"	978'	
				15 1/2"	205'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand from 1405' to 1400'. Mixed and ran 6 sacks cement thru dump bailer.

Mudded hole to 325' - set 25' rock bridge.

Filled hole with 6 yards ready-mix from 300' to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 8 - 1974  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Southwest Casing Pulling Co.  
Address Box 364 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.  
Box 364 Great Bend, Kansas  
(Address)

Subscribed and sworn to before me this 6 day of April, 1974

Sidney Miller  
Notary Public.




COPY

OLNEY P. FLYNN ET AL.  
Orletta Schroeder No. 3.

SIC. 23 T. 18 R. 16W.  
C1/2 NW SE

Total Depth. 3547  
Comm. 6-17-41 Comp. 7-15-41  
Shot or Treated.  
Contractor. J. H. ...  
Issued. 10-18-41

County Wash.



CASING.

15 1/2"	205'	cemented
10"	976'	cemented
7"	3543'	cemented.

Elevation.

Production, Pot. 1107 B.

Figures indicate Bottom of Formations.

clay and sand	70
shale and shells	270
shale	400
sand white	300
red rock	545
sand	580
red rock	780
red rock and sand	965
red rock	968
lime and anhydrite	998
red rock	1210
shale blue	1255
shale	1400
shale and salt	1445
salt	1650
shale and shells	1720
lime and shale breaks	1840
lime and shale	1970
broken lime	2050
lime	2195
shale and shells	2245
lime and shale	2330
lime	2360
shale and red bed	2380
lime	2400
shal. and shells	2475
lime and shale	2705
lime	2785
lime and shale	2870
lime hard	2895
lime	2920
lime broken	3000
shale	3010
lime	3055
lime grey	3060
lime broken	3070
lime brown	3145
lime	3180
lime and shale	3200
lime hard	3310
lime soft	3320
lime hard	3325
lime	3440
shale conglomerate	3470
sand and shale	3490
lime and shale	3505
sand	3519
conglomerate	3525
shale	3531
broken lime	3535
sand	3547
Total Depth.	

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 25 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Swabbed from 2356 24.34 bbls per hr.  
Drilled from 3542 1/2 to 3547.

