

15.165.02134.00.00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Locate well correctly on above
Section Plat

Rush County, Sec. 23 Twp. 18, Rge. 16 (E) (W)
 Location as "NE/CNWSW" or footage from lines NW SE
 Lease Owner: Twin Western Resources Inc.
 Lessee Name: O. Schroeder Well No. #2
 Office Address: 200 E. First St. Suite 518 Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole)
 Date well completed _____ 19____
 Application for plugging filed _____ 19____
 Application for plugging approved _____ 19____
 Plugging commenced 3-22-74 _____ 19____
 Plugging completed 5-11-74 _____ 19____
 Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Leo Massey
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3552' Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	3522'	1725.59'
				10"	977'	
				15 1/2"	202'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made bottom hole plug back with sand to 3500'. Mixed and ran 6 sacks cement thru dump trailer.
 Squeezed hole with 1 sack bulls and 35 sacks gel. Released plug and displaced with 150 sacks cement to base of cellar.

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 15 1974
 CONSERVATION DIVISION
 Wichita, Kansas


Name of Plugging Contractor, Southwest Casing Pulling Co. (If additional description is necessary, use BACK of this sheet)
 Address Box 364 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton ss.

Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
 Box 364 Great Bend, Kansas (Address)
 _____ 19 74

Subscribed and sworn to before me this 13 day of May 1976
 20th October 1976



Sidney D. Miller Notary Public.

Log of Schroeder #2 NW-SE-Sec 23 Twp 18 Range 16 West

Casing Record

16" OD 202' 10 3/4" OD 977' 8" OD 3522'

Soil	0	15	Lime Broken	2795	2850
Sand	15	80	Lime	2850	2885
Shale	80	202	Shale	2885	2895
Red Rock	202	250	Lime	2895	3095
Shale	250	400	Lime Broken	3095	3135
Shale Sand	400	580	Lime	3135	3316
Sand	580	599	Sand	3316	3324
Red Rock	599	665	Lime	3324	3467
Sand Shale	665	850	Conglomerate	3467	3477
Red Rock	850	973	Sand	3477	3549
Lime	973	1035			
Red Rock	1035	1165	7" OD set at 3522'		
Shale Lime	1165	1422	14 1/2 M cubic ft gas at 3524		
Salt Shale	1422	1658			
Lime Broken	1658	1723	First oil at 3524		
Shale Shells	1723	1815			
Lime Hard	1815	1884			
Lime Broken	1884	1900			
Lime	1900	1935			
Lime Broken	1935	1964			
Lime	1964	2100			
Lime Broken	2100	2120			
Lime	2120	2250			
Sand	2250	2270			
Lime Sandy	2270	2280			
Shale	2280	2295			
Lime	2295	2355			
Lime Broken	2355	2511			
Shale Shells	2511	2700			
Lime	2700	2737			
Shale Shells	2737	2795			

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 25 1974
 CONSERVATION DIVISION
 Wichita, Kansas