

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15.113.04593.0000

API NUMBER none

LEASE NAME E. A. Hetzke

WELL NUMBER 2

4950 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 29 TWP. 21 RGE. 1 (X) or (W)

COUNTY McPherson

Date Well Completed 7/2/36

Plugging Commenced 4/17/86

Plugging Completed 4/17/86

LEASE OPERATOR Hess Oil Company

ADDRESS P. O. Box 1009, McPherson, KS 67460

PHONE# (316) 241-4640 OPERATORS LICENSE NO. 5663

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Salina

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation Hunton Depth to Top 3289' Bottom 3311' T.D. 3311'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		141'	0	13"	141'	none
Hunton		3291'	0	7"	3291'	150'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Cleaned out well to 246'. Could not go deeper.

Cemented from 246' to surface with 8 yards of cement and sand mix.  
(6 sacks)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor same as above License No. STATE CORPORATION COMMISSION

Address MAY 19 1986

STATE OF Kansas COUNTY OF McPherson, ss.

CONSERVATION DIVISION  
Wichita, Kansas

Bryan Hess (Employee of Operator) or (Operator) of  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,  
statements, and matters herein contained and the log of the above-described well as filed that  
the same are true and correct, so help me God.


(Signature) Bryan Hess

(Address) same

SUBSCRIBED AND SWORN TO before me this 16th day of May, 19 86

Don J. Reichenberger  
Notary Public

My Commission Expires: 11-15-89



COMPLETION REPORT: F. A. Hetzke #2 Located 330' from the ~~South~~ <sup>North</sup> Line and 990' from the ~~East~~ <sup>West</sup> Line in Sec. 29, Twp. 21S. Rng. 1W McPherson County, Kansas.  
CONTRACTOR L. W. Prunty Drilling CO.  
DATE SPUDDED May 30, 1936.  
DATE COMPLETED July 2, 1936.  
ACTUAL DEPTH 3311'  
INITIAL PRODUCTION 1144 Bbls.

6

NATURE OF STRATA	FROM	TO	
Surface-Sand & Shells	0	139	
Lime	139	145	
Shale	145	300	Ran and set 134'9" of 13" OD 50#
Shale & Shells	300	371	LW casing @ 141' 150 sax. cement.
Broken Lime	371	421	
Shale & Shells	421	500	
Broken Lime	500	543	
Shale & Shells	543	697	
Broken Lime	697	807	
Shale & Shells	807	864	
Lime	864	1064	
Shale & Shells	1064	1206	
Shale	1206	1341	
Shale & Shells	1341	1507	
Shale	1507	1617	
Shale & Lime Shells	1617	1737	
Broken Lime	1737	1966	
Shale & Shells	1966	2007	
Shale & Lime Shells	2007	2162	
Broken Lime	2162	2305	
Lime	2305	2675	
Broken Lime	2675	2774	
Shale	2774	2914	Ran & Set 3312'6" of 7" 24# 10Thd
Chat	2914	3070	Smls. Casg. @ 3291'. Cemented with
Lime	3070	3225	300 sax of Atlas and 100 sax Incon
Shale	3225	3289	Cement.
Hunton Lime	3289	3311	

CASING RECORD

SIZE	WEIGHT	AMT. RUN	AMT. PULLED	AMT. LEFT IN	CEMENT USED.
13"	40#	134'9"	NONE		150 sax.
7"	24#	3312'6"	NINE		400 sax.

CHEMICAL RECORD

# Treated w/ 4000 Gal Chemical process acid and 60 bbl. load oil. Time 2 hrs.  
 30 minutes. 390# Pressure.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 10 1936

CONSERVATION DIVISION  
Wichita, Kansas