

KANSAS

FORM CP-3
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-113-20, 773⁴

245 North Water
Wichita, KS 67202

Operator's Full Name Krehbiel Oil

Complete Address 1334 N. Maple, McPherson, Kansas

Lease Name Neufeldt Well No. 1

Location App. SE NE NE Sec. 16 Twp. 21 Rge. 3 (~~East~~) (West)

County McPherson Total Depth 3393'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas License No. 683

Operation Completed: Hour: 4:00 PM Day: 22 Month: January Year: 1981

The above well was plugged as follows: 8 5/8" - 218' - 200 sacks 5 1/2" - 3385' - 50 sacks Top Perf 3325'

Hole Filled with sand to 3300' and cemented with 5
sacks cement. Rock bridge set on fluid from 240' to
220' and hole cemented to base of cellar with 3 1/2
yards ready-mix concrete

2769' of 5 1/2" casing recovered.

RECEIVED
STATE CORPORATION COMMISSION

JAN 27 1981

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Conservation Division Agent

DATE 2-18-81

INV. NO. 44 97-10



Blackstone Drilling, Inc.

Box 1184 • 528 West Kansas • Phone (316) 241-1250
McPHERSON, KANSAS 67460

October 13, 1980

COMPANY: HOMER G. KREMBIEL, SR.
CONTRACTOR: BLACKSTONE DRILLING, INC.
FARM: NEUFELDT #1
LOCATION: Approx. SE NE NE Sec. 16-21-3W,
McPherson, County, Kansas
COMMENCED: October 6, 1980
COMPLETED: October 12, 1980
ELEVATION:

0	to	190	Sand
190	to	225	Blue Shale
225	to	721	Shale
721	to	1180	Shale & Lime
1180	to	1735	Shale
1735	to	2380	Shale & Lime
2380	to	2620	Lime & Shale
2620	to	2780	Shale & Lime
2780	to	2990	Lime
2990	to	3080	Mississippi
3080	to	3165	Lime
3165	to	3365	Shale & Lime
3365	to	3393	Lime
		3393	T. D.

Cut 12 $\frac{1}{2}$ " hole to 218' and run 220' of 8 5/8" surface pipe, cemented with 300 sacks of cement at 218'. Plug down at 11:45 A. M., October 6, 1980. Run 3397' of 5 $\frac{1}{2}$ " casing cemented with 50 sacks of cement at 8 foot off bottom at 3385'. Plug down at 7:00 P. M., October 12, 1980.

TOPS:

Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Neufeldt #1, located on the Approx. SE NE NE Section 16-21-3W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.


P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 13th day of October, 1980.


Johnnie L. Schmidt - Notary Public

