

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Dean & Clark, Inc.

Complete Address: Suite 20 400 N. Woodlawn, Wichita, Kansas 67208

Lease Name Holtsberg Well No. 1

Location C NW SE Sec. 23 Twp. 21 Rge. 23 NE (W)

County Hodgeman Total Depth 4600'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Forbes Casing Pulling Co.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 11:30AM Day 11 Month 7 Year 1969

The Above well was plugged as follows:

- 8 5/8" to 217' circulated w/ cement. 4 1/2" to 4600' cemented.
- Top perforations 4497' Plug bottom w/ sand & 5 sacks cement .
- Top of cement 4400' Mud 4400' to 900'
- Spotted 80 sacks cement 900' to 600' Mud 600' to 220'
- Spotted 30 sacks cement 220' to 120' Mud 120' to 40'
- Plug, Halls & 10 sacks cement 40' to 0'. Company Pump
- Pulled 2500' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edmund Evers
Well Plugging Supervisor

DATE 7/14/69
INV. NO. 82-W