

To: 1 070603
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3447

Operator: Ranken Energy Corporation
Name & Address
3206 Teakwood Lane
Edmond, OK 73013

10-26
API NUMBER 15-083-21,312-0000
SW SW SW, SEC. 17, T 21 S, R 23 W/R
330 feet from S section line
4950 feet from E section line
Lease Name Thelma Well # 1-17''
County Hodgeman 150.80
Well Total Depth 4640 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 213

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241
Address Box 819, Russell, KS 67665

Company to plug at: Hour: 9:45 p.m. Day: 26 Month: 10 Year: 19 88

Plugging proposal received from Tom Larson
(company name) Ranken Energy Corporation (phone) 316-792-3664

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1598-1642'
1st plug at 1640' with 50 sx cement, Elevation 2354'GL
2nd plug at 820' with 80 sx cement, 3rd plug at 240' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:59 p.m. Day: 26 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1640' with 50 sx cement
2nd plug at 820' with 80 sx cement,
3rd plug at 240' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1988
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED
I did not observe this plugging.

DATE 11-3-88
INV. NO. 22866

Signed Dan Soder (TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date. Oct. 15 1988 month day year

API Number 15-083-21,312-0000

OPERATOR: License # 3447 Ranken energy Corporation Name 3206 Teakwood Lane Address Edmond, Oklahoma 73013 City/State/Zip Mr. Tom Larson Contact Person (316) 792-3664 Phone

SW SW SW Sec. 17 Twp. 21 S, Rg. 23 East West 330 4950 Ft. from South Line of Section Ft. from East Line of Section

CONTRACTOR: License # 8241 Emphasis Oil Operations Name Russell, Kansas City/State

(Note: Locate well on Section Plat on reverse side)

Well Drilled For: Well Class: Type Equipment: Oil Storage Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Nearest lease or unit boundary line 330 feet County: Hodgeman Lease Name: Thelma Well # 1-17 Ground surface elevation 2354 feet MSL

IF OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Depth to bottom of fresh water 100' Depth to bottom of usable water 740'

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 09-6-1988 Signature of Operator or Agent Title: President

For KCC Use: Conductor Pipe Required 200' feet; Minimum Surface Pipe Required 200' feet per Alt. X (2) This Authorization Expires 1-10-89 Approved By LKM 10-10-88

EFFECTIVE DATE: 10-15-88

RECEIVED STATE COMMISSION NOV 1 1988

SW SW SW Sec. 17 Twp. 21 S, Rg. 23 East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays) CONSERVATION DIVISION Wichita, Kansas

Table with 4 columns: Plug depth (ft), Formation, Circulation (SX), and Plugging material (e.g., 60-40 Poz w/ 6% gel). Rows include 1st plug @ 1490 ft, 2nd plug @ 750 ft, 3rd plug @ 230 ft, 4th plug @ 40-0 ft, and 5th plug @ ft deep.

Prly @ 4520 am 10-25-88 @ 11:30 AM

PUSHER Bill Owen TD FORMATION SURFACE PIPE 8 3/8" @ 213' ANHYDRITE 1598 ELEVATION 2359 FT. STARTING TIME & DATE COMPLETION TIME & DATE 1st PLUG @ 1640 FT. W/ 50 SX 2nd PLUG @ 820 FT. W/ 80 SX 3rd PLUG @ 240 FT. W/ 40 SX 4th PLUG @ 40 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ 10 SX CEMENT COMPANY TECHNICIAN S.P. 60/40 Poz w/ 6% gel.