

KANSAS

15.165.20486.00-00

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 28 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name General Geothermal, Inc.

Complete Address 5 Deaver Technological Center, Suite 3201, Englewood, Colorado

Lease Name Pranger 'A' Well No. 1

Location NW NW SW Sec. 7 Twp. 18 Rge. (E) (W) 2D

County Rush Total Depth 4165'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor DNB Drilling

Address Wichita, Kansas License No.

Operation Completed: Hour 10 P Day 21 Month 1 Year 1974

The above well was plugged as follows:

RTD 4165' 8 5/8 csg set at Cmt. Mat. comm. W/2% gel.

Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 50 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo T. Mansury
Well Plugging Supervisor

INVOICED

DATE 1/30/74

INV. NO. 8469-W