

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 18 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Luft - Kerbs & Francis

Complete Address: Box 24 Great Bend, Kans

Lease Name Rodia Well No. B-3

Location NE SW NE Sec. 27 Twp. 18 Rge. (E) (W) 16

County Rush Total Depth 3636

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Ace Pipe Pulling

Address: Great Bend, Kans License No. 2

Operation Completed: Hour 5PM Day 13 Month 11 Year 64

The Above well was plugged as follows:

8 5/8" 1057' circulated with cement - 5 1/2" 3636' with 75 sax cement -  
Perf 3610'

Sand back to 3600', set 4 sax cement with dump bailer - pulled 3112' 5 1/2" -  
pumped hole full heavy gel mud ( 35 sax ) followed by 100 sax cement.

Mudding and cementing by Ace Company Pump truck 400# to 200# pump pressure.

I hereby certify that the above well was plugged as herein stated.

DATE 11/18/64  
INV. NO. 185-11

Signed: Edon Kelly  
Well Plugging Supervisor