

2

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
NOV 10 1977
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - - (of this well)

Operator's Full Name J. C. Musgrove, Inc.
Complete Address Box 611, Great Bend, Kansas 67530
Lease Name Schroeder Well No. 1
Location 100' N of SE SW NE Sec. 26 Twp. 18 Rge. (E) (W) 16
County Rusk Total Depth 3580'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Rockhold Engineering, Inc.
Address Box 698, Great Bend, Kansas License No. 670
Operation Completed: Hour 3 P Day 7 Month 11 Year 1977

The above well was plugged as follows:

Total Depth 3580' 8 5/8 csg set 973' cwc 425 sk.
4 1/2 csg set 3579' cw 100 sk cem. Top perf. (3524')
Filled 4 1/2 csg W/sd (3580'-3500') dumped 4 sk cem W/dump bailer. (3500'-3465')
Cutoff & recovered 2886' of 4 1/2 csg.
Sun Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/100 lbs
hulls, released cementing plug & pumped 120 sk 60-40 poz 2% gel & shutin. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 11-10-77
INV. NO. 6181-W