

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 13 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Midway Drilling, Inc.

Complete Address P. O. Box 921 Great Bend, Kansas 67530

Lease Name O. Schroeder Well No. 6

Location CNL SE Sec. 23 Twp. 18 Rge. (E) (W) 16

County Rush Total Depth 3578'

Abandoned Oil Well Gas Well Input Well XX SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 2:30 P Day 8 Month 3 Year 1974

The above well was plugged as follows:

Total Depth 3578' 8 5/8 csg set at 980' cwc

5 1/2 csg set at 3578' cwc 250 sk.

5 1/2 csg perf. (3546-3564)

Filled 5 1/2 csg W/sd (3578-3525) dumped 4 sk cmt W/dump bailer. (3495-3525)

Cutoff and recovered 2235' of 5 1/2 csg.

Filled 8 5/8 csg with mud to 325' -set rock & sand bridge (325-300)

Filled with readymix cement from 300' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. F. Wansley
Well Plugging Supervisor

INVOICED

DATE 3/18/74

INV. NO. 8752-U