

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 15 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Midway Drilling, Inc.

Complete Address P. O. Box 921, Great Bend, Kansas 67530

Lease Name Crowell Well No. 22

Location SW 1/4 NE 1/4 Sec. 23 Twp. 18 Rge. (E) (W) 16

County Rush Total Depth 3555'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 405, Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 3 P. Day 13 Month 4 Year 1974

The above well was plugged as follows:

Total Depth 3555' 10 3/4 csg set at 950' cwg:

7" csg set at 3520' cw 350 sk cement.

Filled 7" csg W/sd (3500-3555) dumped 5 sk cem with dump bailer. (3470-3500)

Cutoff and recovered 1800' of 7" csg.

Filled 10 3/4 csg with mud to 325' -set rock & sand bridge (325-300)

Dumped readymix cement from 300' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/15/74

INV. NO. 8927-W

Signed: Leo F. Massey
Well Plugging Supervisor