

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

3-25-74

MAY 20 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Midway Drilling, Inc.

Complete Address P. O. Box 921 Great Bend, Kansas 67530

Lease Name O. Schroeder Well No. 5

Location C S/2 N/2 SE Sec. 23 Twp. 18 Rge. (E) (W) 16

County Rush Total Depth 3570'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 11:30 A Day 21 Month 3 Year 1974

The above well was plugged as follows:

Total Depth 3570' 12 1/2" csg 120' cwc 115 sk. 8 5/8 csg 984 CW 300 sk cmt.

5 1/2" csg set at 3502' cw 75 sk cmt.

Filled 5 1/2" csg W/sd (3480-3570) dumped 4 sk cmt W/dump bailer. (3450-3480)

Cutoff and recover 1330' of 5 1/2" csg.

Filled 8 5/8 csg with mud to 550' -set rock & sand bridge (450-550)

Dumped readymix cement from 450' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/28/74

INV. NO. 8820-U

Signed: Leo J. Marney  
Well Plugging Supervisor