

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

3-27-74

RECEIVED
STATE CORPORATION COMMISSION
MAR 27 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Midway Drilling, Inc.
Complete Address Box 921, Great Bend, Kansas 67530
Lease Name O. Schroeder Well No. 4
Location C NE SE Sec. 23 Twp. 18 Rge. (E) (W) 16
County Rush Total Depth 3558'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Southwest Casing Pulling
Address Box 436, Great Bend, Kansas 67530 License No. 399
Operation Completed: Hour 3 P Day 26 Month 3 Year 1974

The above well was plugged as follows:

Total Depth 3558' 12 1/2 csg at 179' cwc 10 3/4 csg at 967' cwc
5 1/2" csg set at 3558' cw 75 sk cmt. Perf. (3503-3535)
Filled 5 1/2" csg W/sd (3475-3558) dumped 4 sk cmt W/dump bailer. (3435-3475)
Dakato squeezed & circ. to surface. No pipe recovered.
Set 5 1/2" wood plug at 335' -poured rock & sand bridge (335-320)
Filled with readymix cement from 320' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 3/28/74
INV. NO. 8819-W