



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 8 - 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Midway Drilling, Inc.

Complete Address P. O. Box 921, Great Bend, Kansas 67530

Lease Name O. Schroeder Well No. 3

Location C: E/2 NW SE Sec. 23 Twp. 18 Rge. (E) (W) 16

County Rush Total Depth 3547'

Abandoned Oil Well Gas Well Input Well XX SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 3:30 P Day 5 Month 4 Year 1974

The above well was plugged as follows:

Total Depth 3557' 15 1/2" csg 205' cwc 10 3/4 csg 978' cwc

7" csg set at 3547' cw 200 sk cem.

7" csg perf. (3518'-3529') Top of tbg 1450' -set plug at 1450' -poured 50' sand -
dumped 6 sk cem, with dump bailer.

~~Added 20' csg to 3500' - 3547' dumped 6 sk cem with dump bailer. (3470-3500)~~

Cutoff and recovered 1000' of 7" csg.

Filled 10 3/4 csg with mud to 325' -set rock & sand bridge (325-300)

Dumped readymix cement from 300' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: B. J. [Signature]
Well Plugging Supervisor

INVOICED

DATE 4/9/74

INV. NO. 8900-W