

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 13 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Midway Drilling, Inc.  
Complete Address Box 921, Great Bend, Kansas 67530  
Lease Name O. Schroeder Well No. 2  
Location NW NW SE Sec. 23 Twp. 18 Rge. (E) (W) 16  
County Rush Total Depth 3552'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Southwest Casing Pulling  
Address Box 364, Great Bend, Kansas License No. 399  
Operation Completed: Hour 3 P Day 11 Month 5 Year 1974

The above well was plugged as follows:

Total Depth 3552' 15 1/2 csg 202 cwc 10 3/4 csg 977' cwc  
7" csg set at 3522' cem. unknown.  
Filled 7" csg with sand (3552-3500) dumped 6 sk cem W/dump bailer. (3470-3500)  
Cutoff and recovered 1710' of 7" csg.  
Pumped down 10 3/4 csg with 35 sk gel & water W/100 lbs hulls, -released 10 3/4 plug  
and pumped 150 sk comm cement by Allied Cementing Co. PP:660-800 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Masady  
Well Plugging Supervisor

DATE 5/14/74  
INV. NO. 9098-W