

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 1 - 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Midway Drilling, Inc.

Complete Address P. O. Box 921, Great Bend, Kansas 67530

Lease Name O. Schroeder Well No. 1

Location SW NW SE Sec. 23 Twp. 18 Rge. (E) (W) 16

County Rush Total Depth 3538'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 436 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 2 P Day 29 Month 3 Year 1974

The above well was plugged as follows:

Total Depth 3538' 15 1/2' csg 385' cwc 12 1/2' csgs @ 80' cwc

7" csg set at 3503' Cem. unknown.

Dakato squeezed & circ. to surface. No pipe recovered. Top of tbg fish 1320'.

Set 7" wood plug at 1320' -poured 10' sand -dumped 6 sk cmt W/dump bailer.

Filled 7" csg with mud to 475' -set rock & sand bridge (475-450)

Filled 7" csg with readymix cement from 450' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo L. Massey
Well Plugging Supervisor

INVOICED
DATE 4/2/74
INV. NO. 8847-W