

R
KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 4 - 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Midway Drilling, Inc.

Complete Address Box 921 Great Bend, Kansas 67530

Lease Name J. Schroder Well No. 1

Location NW SW SE Sec. 23 Twp. 18 Rge. (E) (W) 16

County Rush Total Depth 3539'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 2:30 P Day 1 Month 4 Year 1974

The above well was plugged as follows:

Total Depth 3539' 15 1/2" at 222 cwa 10 3/4 csg 982' cwa

7" csg set at 3521' cem: (#)

Filled 7" csg with sand (3500-3539) dumped 6 sk cem W/dump bailer. (3470-3500)

Cutoff and recovered 1603' of 7" csg.

Filled ^{10 3/4 csg} ~~XX"~~ ~~300'~~ with mud to 325' -set rock & sand bridge (325-300)

Filled 10 3/4 csg with ready mix cement from 300' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *Geo. A. Mearns*
Well Plugging Supervisor

INVOICED

DATE 4/4/74

INV. NO. 8883-W