

KANSAS

Y
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Independent Lease Management Co.

Complete Address: 800 Wichita Plaza Wichita, Kansas

Lease Name Koriel "B" Well No. 1

Location NW NW SW Sec. 23 Twp. 18 Rge. 16 (E) (W) X

County Rush Total Depth 3539

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 1 P Day 25 Month 10 Year 1966

The Above well was plugged as follows:

Total Depth 3539'

13" csg. set at 969' cwc.

7" set at 3511' cw 30 sc cement.

7" csg perforat approx. 600' & circ. to surface.

Sand back to 3480'--Dumped 7 sc cem. with dump bailer.

No pipe recovered. Set plug and 20' rock at 310'.

Filled to surface with 3 yds. readymix cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 27 1966
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 10/27/66
INV. NO. 4181-w